



C H A M B E R  
*of*  
C O M M E R C E

N. Santa Monica Reconstruction Project Update  
July 17, 2017

The first segment of reconstructing N. Santa Monica Blvd. (NSMB) between Wilshire Blvd. and Rodeo Dr. will be completed on Saturday, July 8, 2017. The next segment between Rodeo Dr. and Alpine Dr. will start on Monday July 10, 2017. **Traffic will be open to four lanes starting on Saturday at midnight.**

Similar to the first segment, construction will be done in multiple phases. The first phase (Phase A) will start on the Northern side of the boulevard (westbound) and involves the following activities:

- Removal of existing curb and gutter, curb ramps, sidewalks, driveways, cross-gutters, irrigation, catch basins, asphaltic concrete pavement, street light poles and foundations and signal foundations
- Installation of new underground utilities, associated storm drain laterals and main lines, electrical infrastructure (conduits, pull boxes etc.) as well as fiber optic and traffic signal conduits and pull boxes.
- Construction of a new vegetated bio-swale with associated landscape improvements.

This work requires the contractor to occupy an 18' wide working area adjacent the northern curb. To accommodate this work zone, NSMB will be restriped Saturday morning to delineate the work zone and create two westbound and two eastbound lanes.

**The left turn median between Rodeo Dr. and Alpine Dr. will be eliminated. Therefore, you will not be able to make left turns from westbound NSMB to Rexford, Crescent, Canon and Beverly drives. Left turns will be available at Rodeo and Bedford Drives.**

Thank you in advance for your patience and cooperation and encourage you to use alternate routes and exercise caution when driving around the construction area.

To get more information about the project and status updates, please click on the link below to direct you the Project's webpage.

[N. Santa Monica Blvd. Reconstruction Project.](#)

###